

# APOLLO HILL GOLD RESOURCE INCREASES TO 2.24MOZ; 82% CLASSIFED AS MEASURED AND INDICATED

#### **HIGHLIGHTS**

The Measured, Indicated and Inferred Mineral Resource Estimate for the Apollo Hill Gold Project has been updated following completion of a 300 hole, predominantly infill drilling program. This is the second Mineral Resource update in 2025 for the 100%-owned project that is located in the Leonora Region of Western Australia.

The Apollo Hill Mineral Resource now stands at:

- 137.1 Mt @ 0.51 g/t Au for 2,239,000 oz reported above a cut-off grade of 0.20 g/t Au and within a constraining pit shell<sup>1</sup> (Figure 1 and Plate 1) developed using a A\$3,550/oz (US\$2,300/oz) gold price assuming low-cost bulk tonnage mining and heap leach processing. This represents:
  - A 59% increase in the combined higher confidence Measured and Indicated Mineral Resource Classification to 1.84 Moz representing 82% of the total Mineral Resource;
  - o A 10% (200 koz) increase to the previous 2.03 Moz total Mineral Resource.
- The updated Mineral Resource is based on:
  - An additional 300 reverse circulation (RC) holes and 9 diamond drill holes/tails (DD) totalling 55,757 m completed by Saturn within the model area since the previous Mineral Resource in February, 2025.
  - 25 additional metallurgical and geotechnical diamond drill holes (DD) holes, totalling 4,125 m, which were utilised for geological modelling purposes but were not available for use in the updated Mineral Resource estimate.
  - o Continuous improvement in geological, mineralization, and resource modelling.

This Mineral Resource is being utilised to develop the PFS mining inventory and production forecast and inaugural Apollo Hill Ore Reserve, both targeted for release in late CY2025.

Drilling is continuing towards developing a further Mineral Resource update which will provide the basis for a DFS mining inventory and production forecast and updated Ore Reserve, targeted for release in CY2026.

- The 1.84 Moz of Measured and Indicated Mineral Resource defined by Saturn since listing in 2018, was achieved with 207,336 m of RC and diamond drilling. That is 8.9 ounces of gold added and converted for every metre drilled.
- Clear potential exists to continue growing the Apollo Hill Mineral Resource, with mineralisation still open in several directions.
- Significant exploration potential exists beyond the 6 km long Apollo Hill trend on the surrounding 1,000 km² green-fields 100% owned contiguous tenement package. Drilling continues across the Company's land package, with several significant intersections recently returned at nearby discoveries.

Saturn Metals Limited ABN: 43 619 488 498

<sup>&</sup>lt;sup>1</sup> The constraining pit shell was generated from a Whittle pit optimisation using approximated regional mining and processing costs for a heap leach processing scenario run on the resource model using a gold price of AUD\$3,550/oz to generate an economic pit shell to satisfy the JORC Code requirement for a Mineral Resource to have reasonable prospects for eventual economic extraction. Other relevant information is described in the JORC Code Table 1 as appropriate.

Commenting on the Mineral Resource upgrade, Saturn Managing Director Ian Bamborough said:

"This Mineral Resource update is the seventh consecutive upgrade for the Company at our flagship Apollo Hill Gold Project. We continue to make significant steps forward with the resource under a conventional and efficient bulk mining and heap leach processing trajectory.

The Mineral Resource is published within a single, simple, large 'Whittle' pit shell, which demonstrates the potential to realise significant economies of scale and the resulting efficiencies that this will deliver.

Significant improvements in the quality and size of the Mineral Resource through effective drilling continue to bode well for the advancement of our business.

Impressive conversion to the higher confidence Measured and Indicated Mineral Resource Categories provides an expanded basis from which to base the Company's PFS and inaugural Ore Reserve later in CY 2025. There is clear potential for the PFS mining inventory to capture a high proportion of the Mineral Resource.

Completion of this recent major drill phase has provided major leverage to the geological understanding of the deposit, and we currently have rigs on site focused on resource growth, resource in-fill, geotechnical and metallurgical drilling. This drilling will in turn provide the basis of another planned resource estimate in FY 2026 that will ultimately be used to guide an Orel Reserve update which will be the basis for our Definitive Feasibility Study also planned for release in 2026.

Chart 1 shows the consistent growth achieved in the total Apollo Hill Mineral Resource since the Company was incorporated in mid-2017. Chart 1 also illustrates a strong conversion from Inferred to Measured and Indicated Mineral Resource Categories.




Chart 1 – Apollo Hill Total Mineral Resource growth in ounces and growth in Mineral Resource Categorisation since Saturn's incorporation in 2017. <sup>2</sup>

<sup>(</sup>See Saturn ASX announcement dated 12 February 2025 for details of the February 2025 Measured, Indicated and Inferred Mineral Resource of 118.7 Mt @ 0.53 g/t Au for 2,030,000 oz reported above a cut-off grade of 0.20 g/t Au).



2

<sup>&</sup>lt;sup>2</sup> (See Saturn Metals Limited Prospectus available on our website for details of the initial/2017 Inferred Mineral Resource 17.8 Mt @ 0.9 g/t Au for 505,000 oz reported above a cut-off grade of 0.5 g/t Au).

<sup>(</sup>See Saturn ASX Announcements dated 19 November 2018 for details of the 2018 Indicated and Inferred Mineral Resource of 20.7 Mt @ 1.0 g/t Au for 685,000 oz reported above a cut-off grade of 0.5 g/t Au).

<sup>(</sup>See Saturn ASX announcement dated 14 October 2019 for details of the 2019 Indicated and Inferred Mineral Resource of 24.5 Mt @ 1.0 g/t Au for 781,000 oz reported above a cut-off grade of 0.5 g/t Au).

<sup>(</sup>See Saturn ASX announcement dated 28 January 2021 for details of the 2020-2021 Indicated and Inferred Mineral Resource of 34.9 Mt @ 0.8 g/t Au for 944,000 oz reported above a cut-off grade of 0.4 g/t Au).

<sup>(</sup>See Saturn ASX announcement dated 2 May 2022 for details of the 2021-2022 Indicated and Inferred Mineral Resource of 76 Mt @ 0.6 g/t Au for 1,469,000 oz reported above a cut-off grade of 0.23 g/t Au).

<sup>(</sup>See Saturn ASX announcement dated 28 June 2023 for details of the 2023 Measured, Indicated and Inferred Mineral Resource of 104 Mt @ 0.54 g/t Au for 1,840,000 oz reported above a cut-off grade of 0.20 g/t Au).




Figure 1 – Oblique view 3D Representation of the July 2025 Apollo Hill Mineral Resource model and selected nominal constraining pit for reporting shown with topography – Mineral Resource reported within/above the pit shell only.

Saturn Metals Limited (ASX:STN) ("**Saturn**", "**the Company**") is pleased to announce an updated Mineral Resource estimate for the Apollo Hill gold deposit at its 100%-owned Apollo Hill Gold Project located near Leonora in the Western Australian Goldfields.

The upgraded Mineral Resource (Figure 1 and 2, and Table 1) totals 137.1 Mt at 0.51 g/t Au for 2,239,000 oz. This represents a 10% or 200 koz increase in contained gold ounces from the previously published resource.

Importantly, a significant portion of the Apollo Hill resource – 107.4 Mt @ 0.51 g/t Au for 1,753 koz – across the shallower levels of the deposit and pit shell, representing 78% of ounces in the total Mineral Resource, has now been classified as Indicated Mineral Resource.

In addition, a portion of the material at surface is classified as Measured Mineral Resource (4.8 Mt @ 0.54 g/t Au for 83 koz, representing 4% of the total Mineral Resource) and is based on three discrete areas where RC grade control drilling has been used to test the models. Figure 3 illustrates this Measured and Indicated material (combined 82% of the Mineral Resource) relative to the surface and the pit shell.

The near surface location of these high confidence categories provides an excellent basis for the current Pre-Feasibility Study.

The updated Mineral Resource incorporates the assay results of a highly successful 300 Reverse Circulation and 9 Diamond hole 55,757 m extensional and in-fill drilling phase (Figure 4) completed within the model area after the last Mineral Resource upgrade which was published in February 2025. It uses the same cut-off grade of 0.20 g/t Au, the same base estimation process but with further refined grade modelling parameters and the same low-selectivity bulk mining and heap leach processing scenario. The new Mineral Resource is reported within a larger nominal constraining pit shell, along with a refined model block size (rotated 10 m (X) x 25 m (Y) x 10 m (RL)).

There has been a change to block size in the (X) direction to 10 m (and associated selective mining unit) from 20 m used in the February 2025 Mineral Resource Estimate. This change maintains alignment with Apollo Hill's proposed bulk mining parameters whilst allowing additional selectivity around Apollo Hill's hanging wall Lodes and the southern Apollo Hill corridor (around the Ra, Isis and Tefnut zones).

Realistic cost and recovery parameters as used in Saturn's Preliminary Economic Assessment (PEA), (published to the ASX on 17 August 2023) and updated as per Saturn's ASX Announcement on Metallurgy (published on 5 June 2025) act as a guide to reasonable prospects for eventual economic extraction (RPEEE).




Plate 1 – Topographic aerial view of Apollo Hill, July 2025 nominal constraining pit shell<sup>1</sup> boundary and drill pads (looking North); photograph taken on 28 May 2025.

Table 1 July 2025 Apollo Hill Mineral Resource - see also Table 1a for further details.

Mineral Resource		Tonnes	Au	Au metal
Classification	Oxidation	(Mt)	(g/t)	(Kozs)
	Oxide	0.04	0.70	1
Measured	Transitional	1.3	0.57	24
	Fresh	3.5	0.52	59
Subtotal		4.8	0.54	83
	Oxide	0.7	0.51	11
Indicated	Transitional	7.1	0.50	113
	Fresh	99.7	0.51	1629
Subtotal		107.4	0.51	1,753
	Oxide	0.1	0.50	1
Inferred	Transitional	0.9	0.49	15
	Fresh	23.8	0.51	387
Subtotal		24.8	0.51	403
Grand Total		137.1	0.51	2,239

Note: See footnotes in Table 1a. Totals may vary due to rounded figures.

The growth in the Apollo Hill Mineral Resource has been driven by:

- The discovery of additional mineralisation through in-fill and extensional drilling.
- Saturn's improving knowledge of the bulk density, geological controls at the deposit and refinements in the resource modelling techniques have continued to have a positive influence.

Figure 2 highlights the Mineral Resource block model grade distribution in a SW-NE cross sectional view of the 500 m wide mineralised corridor in a central area of the deposit. In addition, the diagram shows the February 2025 Mineral Resource nominal constraining pit shell relative to the new July 2025 Mineral Resource constraining shell. Continuous mineralised zones above the cut-off grade are over 100 m thick in some parts.

Three separate and relatively distinct zones of mineralisation are noted across the deposit on this cross section (location illustrated in plan view on Figure 1). Wide mineralised zones enable highly efficient bulk mining processes to be employed. The new Whittle pit shell drives deeper, and, in some areas, expands further into the eastern hanging-wall to incorporate additional mineralisation. Figure 2 also illustrates the pit optimisation currently bottoming at 50 mRL or 310 m below surface.




Figure 2 – Oblique block model cross-section (South West – North East, A-A<sup>1</sup> on Figure 1 3D diagram) ± 15 m showing gold grade and block locations.




Figure 3 – Measured, Indicated, Inferred Mineral Resource and unclassified mineralization relative to the nominal constraining open pit shell. Blocks illustrated are >0.20 g/t Au (cut-off grade). Material outside of the nominal pit shell and material left as unclassified is not reported.




Figure 4 – Spatial location of new drill hole data used in the July 2025 Mineral Resource estimate.

The Company's **development strategy** is to progress the Apollo Hill deposit towards production through completion of a comprehensive Pre-Feasibility Study within the current half year and directly transition into a Definitive Feasibility Study. The Company is collecting data to progress social, environmental, economic, metallurgical, geotechnical and engineering matters in these studies.

The tactics Saturn will employ within this strategy are as follows:

- Continue to increase the drill density within strategic areas of the current Inferred Mineral Resource area to convert material into the higher confidence Indicated Mineral Resource classification.
- 2. Continued metallurgical testing focussing on process optimisation and variability studies.
- 3. Geotechnical studies.
- 4. Water exploration and borefield development across Saturn's ~976 km² Water Exploration Licence portfolio adjacent to Apollo Hill.
- 5. Processing parameter optimisation.
- 6. Project optimisation studies including consideration of staged development concepts.
- 7. Progress permitting, tenure and social matters.

In parallel with its focus on mine development, the Company is actively maintaining an **exploration strategy** to target further expansion of the Apollo Hill gold deposit and look for new deposits across its regional land package.

The tactics Saturn will employ within this strategy are as follows:

- 1. Continue with resource definition drilling to further upgrade Mineral Resource classification and geological/geotechnical diamond drilling to improve structural and orebody knowledge.
- 2. Test for and demonstrate the size potential of the Apollo Hill Gold system by undertaking further step-out and exploratory drilling along and across the greater geological corridor.
- 3. Explore for new styles of mineralisation and opportunities within the larger Apollo Hill gold system by targeting interpreted geological structures. For example, the importance of north south trending fault and strain zones is now more evident as a control on mineralisation within the Apollo Hill Deposit. The intersection of these strain zones with other structures or the extension of these strain zones will be targeted as a focus for additional mineralisation.
- 4. Maintain a concerted exploration effort within Saturn's ~1,000 km² 100% owned contiguous regional tenement package aimed at making and developing new satellite discoveries with the ultimate goal of sustaining long life mining operations (further drilling planned in 2025).

# Listing Rule 5.8.1.

Pursuant to ASX listing rule 5.8.1, and in addition to the information contained in the attached JORC Code "Tables 1" sections 1 to 3, the Company provides the following details in respect of the Apollo Hill Mineral Resource.

#### Mineral Resource Statement Overview

AMC Consultants Pty Ltd (AMC) was employed to update the Mineral Resource estimate for the Saturn Metals Ltd Apollo Hill gold project for reporting in accordance with the JORC Code. The Mineral Resource estimate used all current and appropriate drilling and metallurgical data collected up to 1 July 2025 for the project.

Saturn Metal's released a Pre-Economic Assessment Mining (Scoping) Study on the 17th of August 2023. The Pre-Economic Assessment highlights the viability of large-scale bulk open pit mining coupled with conventional heap leach processing to produce gold doré on site. This Mineral Resource has been prepared in alignment with this study and Saturn's current bulk mining and heap leach Pre-Feasibility Study.

A summary of the updated July 2025 Apollo Hill Mineral Resource is provided in Table 1(a) below:

Table 1 (a). July 2025 Mineral Resource Statement; 0.20 g/t Au cut-off by oxidation domain within an economic pit shell to represent reasonable prospects for eventual economic extraction.

Mineral Resource		Tonnes	Au	Au metal
Classification	Oxidation	(Mt)	(g/t)	(Kozs)
	Oxide	0.04	0.70	1
Measured	Transitional	1.3	0.57	24
	Fresh	3.5	0.52	59
Subtotal		4.8	0.54	83
	Oxide	0.7	0.51	11
Indicated	Transitional	7.1	0.50	113
	Fresh	99.7	0.51	1,629
Subtotal		107.4	0.51	1,753
	Oxide	0.1	0.50	1
Inferred	Transitional	0.9	0.49	15
	Fresh	23.8	0.51	387
Subtotal		24.8	0.51	403
Grand Total		137.1	0.51	2,239

Notes: Model is mdah2025v2.dm. The model is reported above the 2025 nominal RF1.0 pit optimization shell (ah202506\_ps31\_rf1\_run7\_tr, AUD3,550) for definition of "reasonable prospects for eventual economic extraction" (RPEEE) and 0.20 g/t Au lower cut-off grade for all material types. There is no depletion by mining within the model area. Estimation is by ordinary kriging (OK) for all mineralised zones. The model currently assumes a 10 mE x 25 mN x 10 mRL SMU for bulk open pit low-selectivity mining with grade domains defined using CIK on 5 mE x 12.5 mN x 5 mRL blocks. Processing is by heap leach. The model does not account for mining related edge dilution and ore loss. These parameters should be considered during the mining study as being dependent on grade control, equipment and mining configurations including drilling and blasting. Classification is according to JORC Code Mineral Resource categories. Measured is assigned only to areas having RC grade control drilling. Densities are assigned according to key lithological units and weathering oxidation states with values ranging from 1.7 to 2.9 t/m³. Totals may vary due to rounded figures.

## Location

Apollo Hill (29.15°S and 121.68°E) is located approximately 60 km south-east of Leonora in the heart of WA's goldfields region (Figure 6). The deposit and the Apollo Hill project are 100% owned by Saturn Metals and are surrounded by good infrastructure and several significant gold deposits.




Figure 6 - Apollo Hill location, Saturn Metals' tenements, surrounding gold deposits and infrastructure.

# **District Geology**

The Apollo Hill deposit occurs in the Archean Wiluna-Norseman greenstone belt in a mineralised structure parallel and adjacent to the district scale Keith-Kilkenny Fault system. The tenement holdings are dissected by this district scale lineament, which is a complex system of northwest oriented shearing and faulting. This lineament is known to be associated with gold deposits in the region including Genesis Mineral's Sons of Gwalia Mine some 40-50 km to the northwest, and Northern Star's Carosue Dam Operation approximately 130 km to the south-east (Figure 6).

# **Deposit Geology and Geological Interpretation**

### Lithology

Mineralised rock types include strongly deformed mafic volcanoclastic and schistose rocks to the west (footwall) with relatively undeformed pillow basalt and dolerite to the east (hanging wall). Rock units generally strike north-west and dip at 60° towards the northeast. Gold mineralisation crosscuts lithological units in quartz veinlets but is also found at the contacts of basalts and dolerites. Inter-flow meta-sedimentary rocks, dominantly chert, occur in outcrops commonly less than 5 m thick and 200 m strike length throughout the hanging-wall sequence (Figure 7). In addition, gold occurs in a footwall dolerite within the footwall mafic schists.




Figure 7 – Apollo Hill Geological Interpretation (also see cross section B-B<sup>1</sup> in Figure 8).

#### **Structure**

The Apollo Hill mineralised shear zone is 5 km long and +500 m wide. The shear zone generally dips at 60° to the north-east and approximates to the contact between the mafic hanging-wall and mafic schist/volcaniclastic footwall sequences (Figure 7). Several north-south trending and more vertically orientated strain zones intersect the northeast trending shear zone and provide zones of complication and additional focus form mineralisation. Figure 8 illustrates the schematic structure and geology in cross section.




Figure 8 – Apollo Hill Geological Interpretation in southwest-northeast cross section (+/- 15m) B-B¹ location illustrated in plan view on Figure 7; completed and planned drill holes (current program) also illustrated.

### Veining

Discontinuous sheeted and/or stockwork veinlets associated with the gold and hosted by all rock-types dip at approximately 53° towards 054° (north-east) and towards 134° (southeast). Veinlets vary between a few millimetres and a few centimetres thick. In the mineralised areas, vein density ranges between 2 per metre to 20 per metre. Gold grade is seen to increase with veinlet density. Flatter lying structural zones occur within the deposit and dip at approximately 40° to the east and generally plunge to the north. These mineralized zones, which are up to 5 m in true thickness, are developed across the sequence where they act as a stronger focus for mineralisation (Figure 8). Figure 9 shows a recent mineralised RC intercept where veining and mineral alteration are visible. Ladder veining between sheeted veinlet sets is often associated with the highest-grade intercepts. All veinlets have been deformed to some extent.

#### **Mineralisation**

Relatively coarse gold is noted within the quartz veinlets at Apollo Hill. Gold mineralisation can be broadly focused along the contact between hanging-wall and footwall rock-types. The vein systems define several broad mineralised zones (Apollo, Southern Apollo Hill Corridor (including gold mineralisation in Ra Dolerite), and the Apollo Hill Hanging-wall). Mineralisation contacts appear to be relatively gradational on most sections. Studies suggest a complex gold forming history for Apollo Hill with multiple generations of quartz veins and associated mineralisation. Figure 9 shows a 2025 mineralised RC intercept.




Figure 9 – Recent RC chips from Apollo Hill, showing rock types, veining, and assayed grade in Au g/t; AHRC1143 – 335 m to 345 m @ 5.92 g/t Au<sup>3</sup> highlighted; quartz veining and hydrothermal alteration at lithological contacts – continuity of mineralisation at depth.

<sup>&</sup>lt;sup>3</sup> ASX Announcement 23 April 2025.

#### **Alteration**

Gold mineralisation associated with the broader Apollo Shear zone is characterised by a silicasericite-pyrite alteration assemblage particularly proximal (50 m) to the Apollo Shear (Figure 8 & Figure 9). Gold is noted in association with ankerite around some quartz veins. Epidote is noted around higher grades. An outer alteration zone of chlorite-carbonate ± magnetite is noted. Leucoxene formation is developed in dolerites along much of the Apollo Shear. Figure 9 depicts a recent RC intersection showing alteration around mineralised veinlets.

#### Weathering and Regolith

At Apollo Hill, the depth of the weathering profile is relatively shallow. Where deeper weathering is noted, it is related to structure-induced permeability. The base of complete oxidation ranges between 2 m to 30 m but is typically 10 m to 20 m (Figure 8). The depth to the top of fresh rock ranges from 8 m to 70 m but is typically 20 m to 30 m. There is little evidence for supergene gold enrichment in what is left of the eroded weathering profile. Young alluvial and aeolian sediments on-lap the dipping Archaean stratigraphy at Apollo Hill. Where cover sequences occur, bedrock is covered by a maximum of 20 m of transported alluvium. Fresh rock is known to outcrop at Apollo Hill in many locations.

#### **Drilling and Drilling Techniques**

Since discovery in 1986, several companies have completed drilling on the project including Fimiston Mining NL, Battle Mountain (Australia) Ltd, Homestake Gold of Australia Ltd, Mining Project Investors Ltd (MPI), Hampton Hill Mining NL, Apex Minerals NL, Peel Mining Ltd, and Saturn Metals Ltd. Most of the critical RC and DD holes completed at Apollo Hill can be divided into several main periods: 1988 to 1989, 2003, 2011 and 2018 to 2025.

All holes used directly for the Mineral Resource estimation at Apollo Hill are reverse circulation (RC) or diamond drill (DD) holes completed by Saturn or its predecessor companies since 1986. Drilling at Apollo Hill tends to be on 30 m spaced northeast-southwest fences with drilling along the fences ranging from 12.5 m to 30 m intervals. Three areas (Figure 4) have been tested by 12.5 m spaced RC drilling to determine short-scale variability in grades. Drill spacing is less dense towards the margins of the deposits. Mineralisation is not closed off along strike or at depth.

The Apollo Hill Mineral Resource estimate has used 1,614 diamond and RC drillholes for a total of 237,108 m drilled. The holes have been surveyed (collar locations), downhole surveyed, logged, sampled, and recent core has been photographed. The location of the diamond and RC drillholes used in the Mineral Resource estimate are shown in Figures 3 and 4. The drillholes are surveyed using the GDA94 datum and MGA zone 51 coordinates.

#### **Data Review**

Drillholes are predominantly sampled over the full length of the holes with sample intervals generally 1 m in length, with core sampling considering geological boundaries.

The drillhole data, assay data and quality assurance and quality control (QAQC) data have been compiled since 1986. Since that time, several different laboratories have been used, with a corresponding range of sample preparation, assaying, and QAQC protocols.

Analysis of QAQC data since 1986 did not highlight any matters for concern.

#### Sampling and Sub-sampling Techniques

Measures taken to ensure the representivity of RC sampling include close supervision by geologists, use of appropriate sub-sampling methods, routine cleaning of splitters and cyclones, and RC rigs with enough capacity to provide generally dry samples with reasonable recovery. Where deeper holes have become wet in 2025 RC drilling - drilling switches over to diamond tails to maintain sample integrity and to eliminate the chance of contamination. Data available to demonstrate sample representivity includes RC sample weights, sample recovery, sample consistency, field duplicates,

standards and blanks. RC holes were sampled over 1 m intervals by a cone-splitter mounted to the RC drill rig.

Diamond core was drilled as HQ3 and NQ2 diameters dependant on weathering profile and ground conditions. Core was generally cut in half although some full core sampling (10 holes) has been utilised in 2018 and 2019 to help account for nuggety coarse gold noted in logging. Sample sizes range in size, but generally 1 m intervals were used adhering to geological boundaries where appropriate (minimum 0.3 m to maximum 1.2 m). Sampling was undertaken using QAQC procedures in line with industry best practice. This includes the submission and monitoring of standards, blanks and duplicates at regular intervals within each submission, for RC and Diamond samples.

Reverse Circulation (RC) drilling was conducted with either a 4.5 inch or 5.5 inch face-sampling bit.

All Saturn core was oriented using a Reflex orientation tool which was recorded at the drill site. All core was pieced back together and orientated at the Saturn Core yard at Apollo Hill.

On-going review of the Saturn QAQC data indicates that Saturn's results are satisfactory, and that the drilling database is suitable for use in resource estimates.

The Saturn in-fill drilling supports the previous drill hole data suggesting that there is no problem with the spatial location and tenor of mineralisation defined in the historic drilling.

## Sample Analysis Method

Recent Saturn drilling samples were analysed at Bureau Veritas in Kalgoorlie and by ALS in Perth. A 3kg split sub sample was then pulverised to 85% passing 75 microns using an LM5 pulverising mill, with analysis by 50 g fire assay with AAS finish.

## **Estimation Methodology**

Mineralisation envelopes were constructed on south-west to north-east sections parallel to drilling fences, using a nominal 0.2 g/t Au mineralisation boundary on the raw grade data to define the approximate edges of the mineralised zones. Strings were snapped to drillholes and used for developing wireframes of the mineralisation for the Apollo Hill, Southern Apollo Hill Corridor (including gold mineralisation in Ra Dolerite) and Apollo Hill Hanging-wall mineralised zones. Further refinement of internal dilution within the mineralisation envelopes used conditional indicator kriging (CIK) on 5 m (X) by 12.5 m (Y) by 5 m (RL) blocks to probabilistically define coherent zones of mineralisation and internal dilution. Dynamic anisotropy was utilised in both the Main Lode and Hanging Wall domains to refine mineralisation trends within the model.

Wireframe interpretations for secondary weathering related oxidation and top of fresh rock were incorporated into the model.

Raw sample/assay files were flagged/coded for the interpreted mineralisation zones, oxidation profile and internal domains and then composited to a regular 2 m downhole composite length as a means of achieving a uniform sample support.

Bulk density was generated from a set of 1,704 Archimedean determinations using billets of core. Densities have been assigned based on oxidation state. At Apollo Hill, assigned densities range from 1.7 t/m³ (alluvial/soil) to 2.9 t/m³ (fresh mafic rocks).

Grade estimation has been completed using ordinary kriging (OK) for all mineralised zones (Main Apollo Hill mineralised zone, the Apollo Hill Hanging-wall mineralised zone, and the smaller Ra and Tefnut mineralised zones). The flagged composites were used for estimation of panels within a rotated parent block size which emulates a large-scale selective mining unit (SMU) scale mining block with a dimension of 10 m (X) by 25 m (Y) by 10 m (RL).



#### **Mineral Resource Classification**

A combination of Measured, Indicated and Inferred Mineral Resources has been defined, considering a range of parameters including the robustness of the input data, the confidence in the geological interpretation (the predictability of both structures and grades within the mineralised zones), distance from data, and amount of data available for block estimates within the mineralised zones.

### Metallurgy

Metallurgical test work has been carried out for typical mineralised material at Apollo Hill confirming that the ore is amenable to conventional heap leach gold recovery methods. Ongoing test work by Saturn has confirmed it is possible to achieve gold recoveries from primary ore of up to 75% in a full-scale heap leach scenario. Further test work is ongoing to further optimise the recovery process.

### Reporting

In 2025, STN completed further infill and extensional RC and DD drilling on the deposit and is reporting the resource within a nominal pit shell. Preliminary Whittle pit optimisations using approximated regional mining and processing costs for a heap leach processing scenario have been run on the resource model using a gold price of AUD\$3,550/oz to generate an economic pit shell and cut-off grade. A pit shell representing a revenue factor of 1 was selected as a nominal constraint within which to report the Apollo Hill Mineral Resource, thereby satisfying the JORC Code requirement for a Mineral Resource to have reasonable prospects for eventual economic extraction (RPEEE). Other relevant information is described in the JORC Code Table 1 as appropriate. The Mineral Resource was reported using a 0.20 g/t Au cut-off grade in line with preliminary economic analyses and other similar projects globally. Mining is anticipated to be bulk low-grade mining for processing by simple heap leach processing on 10 m benches.

Changes from the February 2025 Apollo Hill Mineral Resource relate to:

- Additional drilling across strike and down-dip.
- Changes to the interpreted geology and revisions to mineralisation.
- Significant additional bulk density data.
- Changes to the block size used for the OK grade estimate. The parent blocks are now smaller in the X dimension (10 m rather than 20 m) to recognise some more discrete mineralisation in both the hanging wall and Ra zone positions, whilst maintaining 10 m bench height in line with the bulk low grade mining scenario for processing via heap leach.
- Refinement and addition to dynamic anisotropy to more accurately reflect localised structural grade trends in the data.
- Revisions to the resource classification to reflect the significant additional data and some improved consistency in results with the improved/decreased drillhole spacing including variography results. Revised estimation parameters including sub-domain definition.
- Improved confidence in modifying parameters including mineral recovery after test work completed in 2025.
- The same 0.20 g/t Au cut-off grade but with the constraint of the Mineral Resource by a new and larger nominal constraining pit shell influenced by an increasing gold price. It should be noted that the AUD\$3,550/oz gold price used is approximately AUD\$1,500/oz below of the current spot price (9 July 2025) demonstrating a solid Mineral Resource base.

This Announcement has been approved for release by the Board of Directors of Saturn Metals Limited.

IAN BAMBOROUGH Managing Director

#### For further information please contact:

#### **Investors & Corporate:**

Ian Bamborough Managing Director T: +61 (0)8 6234 1114

E: info@saturnmetals.com.au

#### **Media Inquiries:**

Nicholas Read Read Corporate T: +61 (0)8 9388 1474

E: nicholas@readcorporate.com.au

#### **Competent Persons Statements:**

The information in this report that relates to exploration targets, exploration and metallurgical results is based on information compiled by Ian Bamborough, a Competent Person who is a Member of The Australian Institute of Geoscientists. Ian Bamborough is a fulltime employee and Director of the Company, in addition to being a shareholder in the Company. Ian Bamborough has sufficient experience that is relevant to the style of mineralisation and type of deposit under consideration and to the activity being undertaken to qualify as a Competent Person as defined in the 2012 Edition of the 'Australasian Code for Reporting of Exploration Results, Mineral Resources and Ore Reserves'. Ian Bamborough consents to the inclusion in the report of the matters based on his information in the form and context in which it appears.

The information in this announcement that relates to the Apollo Hill Mineral Resource estimate (gold) is based on information compiled and generated by Ingvar Kirchner (IK), an employee of AMC Consultants. Mr Kirchner consents to the inclusion, form and context of the relevant information herein as derived from the original resource reports. Mr Kirchner has sufficient experience relevant to the style of mineralisation and type of deposit under consideration and to the activity which is being undertaken to qualify as a Competent Person as defined in the 2012 Edition of the JORC 'Australasian Code for Reporting of Exploration Results, Mineral Resources and Ore Reserves'.

This document contains exploration results and historic exploration results as originally reported in fuller context in Saturn Metals Limited ASX Announcements, Quarterly Reports and Prospectus - as published on the Company's website. Saturn Metals Limited confirms that it is not aware of any new information or data that materially affects the information on results noted. Announcement dates to refer to include but are not limited to 22 January 2025, 18 February 2025, 23 April 2025, 5 June 2025, 20 June 2025, 1 July 2025.

The following extract from the JORC Code Table 1 is provided for compliance with the Code requirements for the reporting of Mineral Resources:



## **Section 1 Sampling Techniques and Data**

(Criteria in this section apply to the Apollo Hill, Apollo Hill Hanging-wall and Ra and Tefnut exploration areas all succeeding sections).

Table II Extract of JORC Code 2012 Table 1

Criteria	JORC Code Explanation	Commentary	Competent Person
Sampling techniques	specialized industry standard measurement tools appropriate to the minerals under	sample representivity includes RC sample weights, sample recovery, sample consistency, field duplicates, standards and blanks.  RC holes were sampled over 1 m intervals using a cone-splitter mounted to the RC drill rig. RC samples were analyzed by Bureau Veritas and ALS in both Kalgoorlie and Perth. At the laboratories the samples were oven dried and crushed to 90% passing 2 mm, and pulverized to 95% passing 106 microns, with analysis by 50 g fire assay.  RC samples were generally taken at 1m intervals. Historically some samples were	IB
Drilling techniques	Drill type (e.g. core, reverse circulation, open-hole hammer, rotary air blast, auger, Bangka, sonic, etc) and details (e.g. core diameter, triple or standard tube, depth of diamond tails, face-sampling bit or other type, whether core is oriented and if so, by what method, etc.).	Diamond core was HO3 of NO2 diameter core. All RC drillholes were surveyed by	IB
Drill sample recovery	Method of recording and assessing core and chip sample recoveries and results assessed.  Measures taken to maximise sample recovery and ensure representative nature of the samples.	RC sample recovery was visually estimated by volume for each 1 m bulk sample bag and recorded digitally in the sample database. Very little variation was observed. Measures taken to maximize recovery for RC drilling included use of face sampling bits and drilling rigs of sufficient capacity to provide generally dry, high recovery	IB



Criteria	JORC Code Explanation	Commentary	Competent Person
	Whether a relationship exists between sample recovery and grade and whether sample bias may have occurred due to preferential loss/gain of fine/coarse material.	samples. RC sample weights indicate an average recovery of 85% to 95% and were dry.	
		The cone splitter was regularly cleaned with compressed air at the completion of each rod.	
		The RC Drilling was completed using auxiliary compressors and boosters to keep the hole dry and ensure the sample was lifted to the sampling equipment as efficiently as possible. The cyclone and cone splitter were kept dry and clean, with the cyclone cleaned after each drillhole and the splitter cleaned after each rod to minimize down-hole or cross-hole contamination. The 2.5-3 kg calico bag samples representing 1 m were taken directly from the cyclone and packaged for freight to Kalgoorlie. The calico represents both fine and coarse material from the drill rig.	
		Diamond core recovery was measured and recorded for each drill run. The core was physically measured by tape and recorded for each run. Core recovery was recorded as percentage recovered. All data was loaded into the STN database.	
		Diamond drilling utilized drilling additives and muds to ensure the hole was conditioned to maximize recoveries and sample quality.	
		There was no observable relationship between recovery and grade, or preferential bias between hole-types observed at this stage.	
		There was no significant loss of core reported in the mineralised parts of the diamond drillholes to date.	
Logging	Whether core and chip samples have been geologically and geotechnically logged to a level of detail to support appropriate Mineral Resource estimation, mining		IB
	studies and metallurgical studies.	RC Chip trays and Diamond Core trays were photographed.	
	Whether logging is qualitative or quantitative in nature. Core (or costean, channel, etc) photography.	The logging is qualitative in nature and of sufficient detail to support the current interpretation.	
	The total length and percentage of the relevant intersections logged.		
Sub-sampling techniques and sample preparation	If core, whether cut or sawn and whether quarter, half or all core taken.  If non-core, whether riffled, tube sampled, rotary split, etc. and whether sampled wet or dry.  For all sample types, the nature, quality and appropriateness of the sample preparation technique.	RC holes were sampled over 1 m intervals by cone-splitting. RC sampling was closely supervised by field geologists and included appropriate sampling methods, routine cleaning of splitters and cyclones, and rigs with sufficient capacity to provide generally dry, high recovery RC samples. Sample quality monitoring included weighing RC samples and field duplicates.	IB
	Quality control procedures adopted for all sub-sampling stages to maximise representivity of samples.	Core was cut in half and submitted to the laboratory. Historically some full core samples have been submitted.	
	Measures taken to ensure that the sampling is representative of the in situ material collected, including for instance results for field duplicate/second-half sampling. Whether sample sizes are appropriate to the grain size of the material being sampled.	Assay samples were crushed to 90% passing 2 mm. A 3kg split sub sample was then pulverised to 85% passing 75 microns using an LM5 pulverising mill, with analysis by 50 g fire assay with AAS finish. Assay quality monitoring included reference standards and inter-laboratory checks assays.	
	sampieu.	Duplicate samples were collected every 40 samples, and certified reference material and blank material were inserted every 25 samples.	
		The project is at an early stage of evaluation and the suitability of sub-sampling methods and sub- sample sizes for all sampling groups has not been comprehensively established. The available data suggests that sampling procedures provide sufficiently representative sub-samples for the current interpretation.	



Criteria	JORC Code Explanation	Commentary	Competent Person
	The nature, quality and appropriateness of the assaying and laboratory procedures used and whether the technique is considered partial or total.  For geophysical tools, spectrometers, handheld XRF instruments, etc., the parameters used in determining the analysis including instrument make and model, reading times, calibrations factors applied and their derivation, etc.  Nature of quality control procedures adopted (e.g. standards, blanks, duplicates, external laboratory checks) and whether acceptable levels of accuracy (i.e. lack of bias) and precision have been established.		IB
	The verification of significant intersections by either independent or alternative company personnel.  The use of twinned holes.  Documentation of primary data, data entry procedures, data verification, data storage (physical and electronic) protocols.  Discuss any adjustment to assay data.	No independent geologists were engaged to verify results. STN geologists were supervised by the company's Exploration Manager. No adjustments were made to any assays of data.  Logs were recorded by field geologists on hard copy sampling sheets which were entered into spreadsheets for merging into a central SQL database.  Laboratory assay files were merged directly into the database. The project geologists routinely validate data when loading into the database.	IB
Location of data points	Accuracy and quality of surveys used to locate drillholes (collar and down-hole surveys), trenches, mine workings and other locations used in Mineral Resource estimation.  Specification of the grid system used.  Quality and adequacy of topographic control.		IB
Data spacing and distribution	Data spacing for reporting of Exploration Results.  Whether the data spacing and distribution is sufficient to establish the degree of geological and grade continuity appropriate for the Mineral Resource and Ore Reserve estimation procedure(s) and classifications applied.  Whether sample compositing has been applied.	Apollo Hill mineralisation has been tested by generally 30 m spaced traverses of south- westerly inclined drillholes towards 225°. Across strike spacing is variable. Material within approximately 50 m of surface has been generally tested by 12.5 m to 30 m spaced holes, with deeper drilling ranging from 30 m to greater than 60 m spacing.  The data spacing is sufficient to establish geological and grade continuity.	IB
	Whether the orientation of sampling achieves unbiased sampling of possible structures and the extent to which this is known, considering the deposit type. If the relationship between the drilling orientation and the orientation of key mineralised structures is considered to have introduced a sampling bias, this should be assessed and reported if material.	Detailed orientations of all short-scale mineralised features have not yet been confidently established. The majority of the drillholes were inclined at around 60° to	IB
Sample security	The measures taken to ensure sample security.	Apollo Hill is in an isolated area, with little access by the general public. STN's field sampling was supervised by STN geologists. Sub-samples selected for assaying were collected in heavy-duty poly-woven bags which were immediately sealed. These bags were delivered to the assay laboratory by independent couriers, STN employees or contractors.	ΙΒ
		Results of field duplicates, blanks and reference material, and the general consistency of results between sampling phases provide confidence in the general reliability of the drilling data.	
Audits or reviews	The results of any audits or reviews of sampling techniques and data.	The Competent Person independently reviewed STN sample quality information and database validity. These reviews included consistency checks within and between database tables and comparison of assay entries with original source records for	IB



Criteria	JORC Code Explanation	Commentary	Competent Person
		STN's drilling. These reviews showed no material discrepancies. The Competent Person considers that the Apollo Hill drilling data has been sufficiently verified to provide an adequate basis for the current reporting of exploration results.	

Section 2 Reporting of Exploration Results (Criteria listed in the preceding section also apply to this section).

Criteria	JORC Code Explanation	Commentary	Competent Person
	Type, reference name/number, location and ownership including agreements or material issues with third parties such as joint ventures, partnerships, overriding royalties, native title interests, historical sites, wilderness or national park and environmental settings.  The security of the tenure held at the time of reporting along with any known impediments to obtaining a licence to operate in the area.	tenements, along with certain other tenure, are the subject of a 5% gross over-riding royalty (payable to HHM) on Apollo Hill gold production exceeding 1 Moz. M39/296	IB
Exploration done by other parties	Acknowledgment and appraisal of exploration by other parties.	RC and diamond drilling by previous tenement holders provides around 14% of the estimation dataset. The data is primarily from RC and diamond drilling by Battle Mountain, Apex Minerals, Fimiston Mining, Hampton Hill, Homestake, MPI and Peel Mining.	IB
Geology	Deposit type, geological setting and style of mineralisation.	The Apollo Hill project comprises two deposits/trends: the main Apollo Hill deposit comprised of the 'Main lode' and 'Hanging Wall Lodes in the northwest of the project area, and the Southern Apollo Hill Corridor trend, comprised of the Wadget-Ra-Iris-Tefnut lodes in the south. Gold mineralisation is associated with quartz veins and carbonate-pyrite alteration along a steeply north-east dipping contact between a schist unit to the west, and mafic dominated volcanic and intrusive rocks to the east. The combined mineralised zones extend over a strike length of approximately 3 km and have been intersected by drilling to approximately 500 m vertical depth. The depth of complete oxidation averages around 4 m with depth to fresh rock averaging around 21 m.	IB
Drillhole Information	A summary of all information material to the understanding of the exploration results including a tabulation of the following information for all Material drillholes: easting and northing of the drillhole collar elevation or RL (Reduced Level – elevation above sea level in metres) of the drillhole collar dip and azimuth of the hole down hole length and interception depth hole length  If the exclusion of this information is justified on the basis that the information is not Material and this exclusion does not detract from the understanding of the report, the Competent Person should clearly explain why this is the case.	been included within the body of the announcement or as appendices.  No information has been excluded.	IB



Criteria	JORC Code Explanation	Commentary	Competent Person
Data aggregation methods	In reporting Exploration Results, weighting averaging techniques, maximum and/or minimum grade truncations (eg cutting of high grades) and cut-off grades are usually Material and should be stated.  Where aggregate intercepts incorporate short lengths of high-grade results and longer lengths of low-grade results, the procedure used for such aggregation should be stated and some typical examples of such aggregations should be shown in detail.  The assumptions used for any reporting of metal equivalent values should be clearly stated.	For exploration data, no top-cuts have been applied.  All reported RC and diamond drill assay results have been length weighted (arithmetic length weighting).  No metal equivalent values are used for reporting exploration results.	IB
Relationship between mineralisation widths and intercept lengths	These relationships are particularly important in the reporting of Exploration Results. If the geometry of the mineralisation with respect to the drillhole angle is known, its nature should be reported.  If it is not known and only the down hole lengths are reported, there should be a clear statement to this effect (eg 'down hole length, true width not known').	All drillhole intercepts are measured in downhole meters, with true widths estimated to be about 60% of the down-hole width.  The orientation of the drilling has the potential to introduce some sampling bias (both positive or negative).	IB
Diagrams	Appropriate maps and sections (with scales) and tabulations of intercepts should be included for any significant discovery being reported These should include, but not be limited to a plan view of drillhole collar locations and appropriate sectional views.	Refer to Figures and Tables within the body of the text.	IB
Balanced reporting	Where comprehensive reporting of all Exploration Results is not practicable, representative reporting of both low and high grades and/or widths should be practiced to avoid misleading reporting of Exploration Results.		IB
Other substantive exploration data	Other exploration data, if meaningful and material, should be reported including (but not limited to): geological observations; geophysical survey results; geochemical survey results; bulk samples – size and method of treatment; metallurgical test results; bulk density, groundwater, geotechnical and rock characteristics; potential deleterious or contaminating substances.	There is no other substantive exploration data.	IB
Further work	The nature and scale of planned further work (e.g. tests for lateral extensions or depth extensions or large-scale step-out drilling).  Diagrams clearly highlighting the areas of possible extensions, including the main geological interpretations and future drilling areas, provided this information is not commercially sensitive.	Although not yet planned by STN in detail, it is anticipated that further work will include infill and step out drilling. This work will be designed to improve confidence in and test potential extensions to the current resource estimates. Refer to Figures and diagrams within the body of the text.	IB



# **Section 3 Estimation and Reporting of Mineral Resources**

(Criteria listed in section 1, and where relevant in section 2, also apply to this section).

Criteria	JORC Code Explanation	Commentary	Competent Person
Database integrity	Measures taken to ensure that data has not been corrupted by, for example, transcription or keying errors, between its initial collection and its use for Mineral Resource estimation purposes.	Geological data is stored centrally in a relational SQL database using Aveza software. STN employs a Contract Database Administrator who is responsible for the integrity of the data.	
	Data validation procedures used.	All geological and field data is entered into Microsoft Excel spreadsheets using lookup tables, fixed formatting and validation rules, to promote data integrity and prevent errors within the database.	
		Assay data is received from the laboratory as a direct export and imported into the SQL in its entirety without edits.	
		The database is continually validated by STN employed geologists who validate and audit the data.	
		During the import of data within the Aveza database, a series of validation procedures occur. The database references established lookup tables and triggers validation procedures to ensure that data is valid before being uploaded into the relevant tables.	
		A comparison of all data planned and what is in the database is made, to ensure all logging, collars, surveys, assays and collar pickups check against the actual collar locations.	
		All data was checked visually in 3D to check all collar locations and surveys were correct.	
Site visits	Comment on any site visits undertaken by the Competent Person and the outcome of those visits.	The Competent Person for the drillhole data, QAQC and geology has been to site frequently between listing in 2018 and 2025.	IB, IK
	If no site visits have been undertaken indicate why this is the case.	The Competent Person for the Mineral Resource has been to site during 2024.	
		Surface geology was inspected, as well as drilling, logging, sampling and assaying.	
Geological interpretation	Confidence in (or conversely, the uncertainty of) the geological interpretation of the mineral deposit.  Nature of the data used and of any assumptions made.  The effect, if any, of alternative interpretations on Mineral Resource estimation.  The use of geology in guiding and controlling Mineral Resource estimation.  The factors affecting continuity both of grade and geology.	Mineralisation envelopes were constructed on south-west to north-east sections parallel to drilling fences, using a nominal 0.2 g/t Au mineralisation boundary on the raw grade data to define the edges of the mineralised zones. Strings were snapped to drillholes and used for developing wireframes of the mineralisation. Further refinement of internal dilution within the mineralisation envelopes used conditional indicator kriging (CIK) on 5mE x 12.5mN x 5mRL blocks to probabilistically define coherent zones of mineralisation and internal dilution. The mineralisation envelopes are designed for a bulk mining scenario with a limited requirement for selectivity within the zones and domains.	IK
		Close 12.5 m spaced RC grade control drilling over three test areas (including an upcoming trial pit) has confirmed the general drilling data and model results which adds confidence in the interpretation of the deposit.	
		The lithology contact between the hanging wall mafic and the footwall schist units were interpreted and modelled based on simplified summary geology data provided.	
		The interpretations are based on good quality core and RC drilling, good quality assay data, and satisfactory logging.	



Criteria	JORC Code Explanation	Commentary	Competent Person
		On a local scale, the mineralisation is not highly structured. The veinlet-type stockwork structures related to the mineralisation are not likely to be continuous relative to the scale of the drilling.  Alteration and association with the Apollo Shear contact are material but not limiting to the definition of mineralisation. Mineralisation occurs both along the shear and contact and within surrounding host rock-types.	
		On a broad scale, the mineralised zones are wide and relatively persistent along strike and down dip, but with erratic local grades and complex structure within the zones.	
Dimensions	The extent and variability of the Mineral Resource expressed as length (along strike or otherwise), plan width, and depth below surface to the upper and lower limits of the Mineral Resource.	Apollo Hill mineralisation has an approximate north-west to south-east strike length of 1.4-5 km, variable width of up to 400 m (including the similar Hanging Wall Zone), and down dip extent of more than 600 m.	IK
		Ra mineralisation is fragmented along a north-west to south-east strike length of 2.1 km, variable width of up to 25 m, and down dip extent of up to 300 m.	
		Tefnut mineralisation is variable with some evidence of an <i>en echelon</i> arrangement and appears to have a north-west to south-east strike length of 500 m, variable widths of up to 20 m, and down dip extent of up to 250 m.	
		Mineralisation extends to near-surface, truncated in some area by a thin layer of barren transported cover sediments. The mineralisation is not closed-off by the resource definition drilling either along strike, across strike to the north-east or downdip, although a decreasing grade trend along strike at the current limits is observed.	
Estimation and modelling techniques	and parameters used.  The availability of check estimates, previous estimates and/or mine production records and whether the Mineral Resource estimate takes appropriate account of such data.	The new model uses ordinary kriging (OK) to achieve a result suitable for large-scale low-selectivity mining and processing scenario. OK is used to estimate a panel-sized SMU model where panel dimensions are similar to nominal drillhole spacings. The estimation parameters used are appropriate for a gold deposit with highly variable grade, and uncertain continuity. Data was domained according to the key mineralised zones as well as internal domaining for the Apollo Hill main zone and Hangingwall zone. Extents were strongly guided by geology and grades.  Datamine Studio RM and ISATIS 2018 were used for modelling, variography and estimation.	IK
	The assumptions made regarding recovery of by-products.  Estimation of deleterious elements or other non-grade variables of economic significance (eg sulphur for acid mine drainage characterisation).  In the case of block model interpolation, the block size in relation to the average sample spacing and the search employed.	Previous estimates using localised multiple indicator kriging (LMIK) and restricted ordinary kriging (ROK) exist and have been considered during modelling. The new model incorporates additional infill and extension drilling. There is no previous mining at Apollo Hill.	
	Any assumptions behind modelling of selective mining units.  Any assumptions about correlation between variables.	There is insufficient data to estimate any deleterious elements or by-products. Sulfide content is very low.	
	Description of how the geological interpretation was used to control the resource estimates.	The SMU block size into which the OK estimate is localized is based on 315° rotated 10 m by 25 m by 10 m blocks and is considered a reasonable SMU for the scale of the deposit and proposed medium to large scale open pit low-selectivity mining	
	Discussion of basis for using or not using grade cutting or capping.  The process of validation, the checking process used, the comparison of model data	method. The SMU size may be reviewed should the proposed mining scenario change.	
	to drillhole data, and use of reconciliation data if available.	The estimation parameters used are appropriate for a gold deposit with highly variable grade, and uncertain continuity. Estimation parameters and search parameters were deliberately selected to best estimate the model without creating undue conditional bias in conjunction with the large SMU blocks. Parameters and	



Criteria	JORC Code Explanation	Commentary	Competent Person
		estimation results were validated via appropriate check methods. Parameters are described in the technical report.	
		The resource estimate was constrained within the modelled mineralisation envelopes and domains to limit extrapolation of grade. The mineralisation envelopes considered available geological data during construction. The thin weathering related oxidation divisions were modelled but, in most areas had inadequate data to allow separate estimation. There were not apparent material grade differences between the various oxide and transitional zones relative to the fresh material and hence the oxidation domains were not used as sub-domains of the mineralized zones.	
		High-grade cuts of 18, 19 and 24 g/t Au were applied to the Apollo Hill main zone, the Hanging Wall zone, and Ra zone Au composite data respectively. As there were no obvious outliers in the small amount of Tefnut Au composite data, no high-grade cut was applied.	
		Validation was completed using the comparison of the OK results to previous ROK estimates, and statistical comparison of data and estimated grades. Further validation using modified swath plots and visual review of grade mapping between the models and the drilling data was conducted.	
		Only gold was estimated.	
		No assumptions are made regarding recovery of by-products.	
		Previous Mineral Resources for Apollo Hill were generated by AMC in 2018, 2019, 2020, 2021,2022, 2023 and February 2025.	
Moisture	Whether the tonnages are estimated on a dry basis or with natural moisture, and the method of determination of the moisture content.	Tonnages are estimated using dry bulk density values.	IK
Cut-off parameters	The basis of the adopted cut-off grade(s) or quality parameters applied.	The July 2025 Mineral Resource estimate for Apollo Hill has been reported at a cutoff of 0.2 g/t Au for all material types, based on economic parameter checks, pit optimization analysis and similar cut-offs for other projects with this style of mineralisation. Preliminary Whittle pit optimizations using approximated regional mining and processing costs for multiple processing scenarios have been run on the resource model using a gold price of AUD\$3,550/oz to generate a range of pit shells and cut-off grades. The selected revenue factor 1 nominal constraining pit shell currently represents a bulk mining and heap leach processing scenario.	
		The project is at an early stage. No mining studies have been completed. It is probable that the cut-off grade, SMU selection and reporting parameters may be revised in the future.	
Mining factors or assumptions	dimensions and internal (or, if applicable, external) mining dilution. It is always necessary as part of the process of determining reasonable prospects for eventual economic extraction to consider potential mining methods, but the assumptions	Mining is assumed to be on either 5 m flitches or a single 10 m bench with a current minimum selective mining unit (SMU) dimension of 10 m by 25 m by 10 m based on RC grade control or similar. This is assumed based on other projects having a similar style of mineralization.	IK
	made regarding mining methods and parameters when estimating Mineral Resources may not always be rigorous. Where this is the case, this should be reported with an explanation of the basis of the mining assumptions made.	Preliminary Whittle pit optimizations using approximated regional mining and processing costs for multiple processing scenarios have been run with a view to open pit mining on 10 m benches and 5 m flitches. For this purpose Whittle pit optimizations were calculated on a 5 m bench height version of the main 10 m wide by 25 m long by 10 m bench height panel resource model using a gold price of AUD\$3,550/oz to generate a range of pit shells and cut-off grades. A pit shell for a heap leach scenario representing a revenue factor 1 was selected as a nominal	



Criteria	JORC Code Explanation	Commentary	Competent Person
		constraint within which to report the Apollo Hill Mineral Resource on the original 10 m wide by 25 m long by 10 m bench height model, thereby satisfying the JORC Code requirement for a Mineral Resource to have reasonable prospects for eventual economic extraction.	
		The project is at an early stage. No mining studies have been completed. It is probable that the cut-off grade, mining scenarios including SMU selection, and reporting parameters may be revised in the future.	
Metallurgical factors assumptions	The basis for assumptions or predictions regarding metallurgical amenability. It is always necessary as part of the process of determining reasonable prospects for eventual economic extraction to consider potential metallurgical methods, but the assumptions regarding metallurgical treatment processes and parameters made when reporting Mineral Resources may not always be rigorous. Where this is the case, this should be reported with an explanation of the basis of the metallurgical assumptions made.	Metallurgical assumptions for all material types are based on existing test-work that indicate good recoveries ranging from 83.6% in oxide material, 85.8% in transitional Basalt/Dolerite material, 82.9% in transitional Mafic Schist material, 77.7% in fresh Basalt/Dolerite material and 72.3% in fresh Mafic Schist material. These recoveries are based on using conventional stage crushing and High-Pressure Grinding Rolls (HPGR) for a heap leach scenario as advised by STN.  Test-work is on-going.	IK
		Further analytical work and modelling may be required to differentiate ore types.	
Environmental factors assumptions	Assumptions made regarding possible waste and process residue disposal options. It is always necessary as part of the process of determining reasonable prospects for eventual economic extraction to consider the potential environmental impacts of the mining and processing operation. While at this stage the determination of potential environmental impacts, particularly for a greenfields project, may not always be well advanced, the status of early consideration of these potential environmental impacts should be reported. Where these aspects have not been considered this should be reported with an explanation of the environmental assumptions made.	options. The project is at an early exploration stage and no mining studies have been completed.  Typical open pit mining and heap leach processing scenarios would require generation of waste dumps and permanent leach pads.	IK
Bulk density	Whether assumed or determined. If assumed, the basis for the assumptions. If determined, the method used, whether wet or dry, the frequency of the measurements, the nature, size and representativeness of the samples.	Dry bulk densities are based on 1,704 analyses of Apollo Hill core billets. It is possible that additional data will modify the averaged density values that were applied to the model as below.	IK
	The bulk density for bulk material must have been measured by methods that adequately account for void spaces (vugs, porosity, etc), moisture and differences between rock and alteration zones within the deposit.  Discuss assumptions for bulk density estimates used in the evaluation process of the different materials.	STN concur that the following rounded density values are appropriate:	
Classification	The basis for the classification of the Mineral Resources into varying confidence categories.  Whether appropriate account has been taken of all relevant factors (ie relative confidence in tonnage/grade estimations, reliability of input data, confidence in continuity of geology and metal values, quality, quantity and distribution of the data). Whether the result appropriately reflects the Competent Person's view of the deposit.	<ul> <li>Use of good quality diamond core and RC data for data used in the resource estimate.</li> </ul>	IK



Criteria	JORC Code Explanation	Commentary	Competent Person
		<ul> <li>Data quality, variability, and analytical data.</li> <li>Bulk density data and representivity for rock-types and the style of mineralisation. The use of average densities based on the oxidation and summary rock-type divisions.</li> <li>Variography.</li> <li>Estimation statistics (number of samples used, distance to data, and estimation pass).</li> <li>Confidence in the interpretations.</li> <li>Three test areas drilled with 12.5 m spaced RC grade control drilling were tightly classified as Measured Mineral Resource. This includes a proposed trial pit area.</li> <li>Some areas of the deposit are moderately to well drilled for a gold deposit, but the mineralisation is not highly structured nor visual. Drilling fences are usually on 25-30 m to 50-60 m intervals with similar spaced drilling along the fences. There remain gaps in the drilling in some key areas.</li> <li>The mineralisation interpretation is extrapolated to a limited distance past the bottom of drilling — usually no more than 50 m to 100 m. Most of the extrapolated areas tend to be left as unclassified in the models.</li> <li>The estimate has been classified as Measured Mineral Resource in three areas of close spaced (12.5 x 12.5m centred) RC grade control drilling. The core of the mineralisation has been classified as Indicated Mineral Resource which is demonstrated by coherent zones of mineralisation with relatively close spaced drilling. The estimate is classified as Inferred Mineral Resource at the edges of the mineralisation along strike and down dip.</li> <li>Background and waste portions of the model have not been classified.</li> </ul>	
Audits or reviews	The results of any audits or reviews of Mineral Resource estimates.0	The Mineral Resource has not been externally audited or reviewed.	IK
Discussion of relative accuracy/ confidence	Where appropriate a statement of the relative accuracy and confidence level in the Mineral Resource estimate using an approach or procedure deemed appropriate by the Competent Person. For example, the application of statistical or geostatistical procedures to quantify the relative accuracy of the resource within stated confidence limits, or, if such an approach is not deemed appropriate, a qualitative discussion of the factors that could affect the relative accuracy and confidence of the estimate. The statement should specify whether it relates to global or local estimates, and, if local, state the relevant tonnages, which should be relevant to technical and economic evaluation. Documentation should include assumptions made and the procedures used.  These statements of relative accuracy and confidence of the estimate should be compared with production data, where available.	methods will be applied in conjunction with processing by heap leach.	IK



Criteria	JORC Code Explanation	Commentary	Competent Person
		mineralisation and possible precision issues noted with repeat or duplicate samples.	
		<ul> <li>Accuracy of averaged bulk density data and porosity/moisture assumptions. Mineralisation and lithology may prove to be more variable than the current scale of drilling and limited density data suggest.</li> </ul>	
		<ul> <li>Selectivity and cut-off grades may vary in future according to mining studies.</li> </ul>	
		<ul> <li>There has been no statistical or geostatistical determination of relative accuracy or confidence due to the lack of stationarity in the data and moderate quality variography in some directions.</li> </ul>	
		The resource classification is considered reasonable based on validation through multiple processes, including visual and graphical review of the estimates.	
		The mineralised area is drilled at a semi-regular spacing and while local variance to the estimate may occur, there is a moderate-to-high degree of confidence in the overall estimate supported by the 2021 and 2023 RC grade control drilling test areas.	
		The primary mineralised zones are moderately defined by drilling, constrained to an interpretation that reflects the broad geological control on grade, and appropriately estimated.	
		The project has no production history for comparison of the model results.	

